

SECTION 102 - TRAFFIC CONTROL

102.1 GENERAL

All traffic control devices and traffic patterns shall conform to the standards in the Manual of Uniform Traffic Control Devices (MUTCD) and the Virginia Work Area Protection Manual unless shown otherwise on the plans.

102.1.1 Referenced Specifications are referred to by abbreviation as follows:

- A. Manual of Uniform Traffic Control Devices (MUTCD)
- B. Virginia Department of Transportation (VDOT)
- C. Virginia Work Area Protection Manual (VWAPM)

102.1.2 The contractor is responsible for providing the required signage and cones.

102.1.3 All signage and traffic control shall be subject to the City's approval. No rerouting of traffic or street closings will be done without prior approval from the City.

102.1.4 All traffic cones are to be 36" tall and clean.

102.1.5 When left unattended, any work zone adjacent to a City street shall have lighted barricades every 30'. No open excavations will be permitted overnight in a City right-of-way.

102.1.6 Rerouting of traffic shall be delineated with traffic cones.

102.1.7 Flagmen must be used when stopping traffic and for equipment entering and exiting a work zone.

102.1.8 All flagmen shall be certified by VDOT and be in possession of a valid flagging card.

102.2 MEASUREMENT AND PAYMENT

When listed as a separate bid item, Traffic Control will be paid for as a lump sum item. Payment will be made as a percentage of the associated items that are completed. When there is not a separate bid item for Traffic Control, it will be considered incidental to all other work and the cost distributed accordingly.